BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

BBMP/2015-16/OW/WORK_INDENT21304

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/03/2015-16 Dated: 08-03-2016

Approved Tender Schedule - B

Item No:10

Name of Work:Asphalting to cross roads and main roads in Someshwaranagara in ward no:04

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri N LOKANATHREDDY	
				Rate	Rupees in words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no 138, PWD SR 2014-15)	Cum	457.5	75.0	Rupees seventy five and paise zero only
2	Removing B.S slab of drain and stacking	Sqm	565.95	10.0	Rupees ten and paise zero only
3	Refixing stone slabs of drains and pointing in CM(1:3)	Sqm	565.95	19.56	Rupees Ninteen and paise fifty six only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms thick	Sqm	242.55	639.0	Rupees six hundred thirty nine and paise zero only
5	KSRRB 4.1:6Providing and laying in position plain cement concrete mix 1:2:4 with cement @240kgs, with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted,in foundation,plinth and cills,including cost of all materials, labour, HOM of machineries, curing complete as per specifications. Specification no	Cum	55.16	5327.0	Rupees five thousand three hundred twenty seven and paise zero only
6	KSRB 5-14: Providing and constructing precast concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.27)	Cum	98	993.0	Rupees nine hundred ninty three and paise zero only
7	KSRB 5-15: Providing and constructing Non load bearing wall with cement concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x10x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.28)	Cum	98	724.0	Rupees seven hundred twenty four and paise zero only
8	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge (Approved Data Rate).	Cum	330.75	1498.0	Rupees one thousand four hundred ninety eight and paise zero only
9	KSRRB M400-17: Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification: 406 (PWD SR 2014-15 P N 154 It 20.18)	Cum	101.99	1438.0	Rupees one thousand four hundred thirty eight and paise zero only
10	KSRRB M500-6,Providing and applying primer coat with S.S.bitumen emulsion on prepared surface of granular base such as WBM,WMM including cleaning of road surfase and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH SpecificationsNo502 (	Cum	1551.62	35.0	Rupees thirty five and paise zero only

11	KSRRB M500-18 Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading,premixed with bituminous binder and filler, transporting the hot mix to work site laying with a paver finisher to the required grade,levell and alignment, rollingwithsmoothwheeled,vibratoryandtandemrollers to achievethe desired compactionasperMORTHSpecificationclauseno508completeinallrespectscompleteasperspecifications.using10012 0THcapacity H.M.P with sensor paver gradingI(35-40mm) with 4.5% RMB55grade	Cum	52.68	10195.0	Rupees ten thousand one hundred ninty five and paise zero only
12	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1 Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2014-15)	Cum	457.5	68.0	Rupees sixty eight and paise zero only

N. Lokanath Reddy

Signature of the contrator

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.